
APPENDIX 1

Event Display Boards

PLANNING THE FUTURE OF OUR LIQUID WASTE

Liquid Waste Management Plans are a tool used by communities to plan for the long-term management of their wastewater. They include engineering study, environmental assessment, financial analysis and significant public consultation. In 2018, the CVRD kicked off the Comox Valley Sewer Service Liquid Waste Management Plan:



DECISIONS ABOUT OUR WASTEWATER

The LWMP was an intensive process that led to some clear decisions about the future of our wastewater infrastructure. These included:

PROVIDE SECONDARY TREATMENT FOR ALL FLOWS

- The preferred treatment option selected will see secondary treatment to all flows as
 the system does currently. Upgrades and expansion to existing components will occur to
 increase capacity and comply with regulations over time.
- Disinfection to achieve 'recreational' standards will be added as a new component to the treatment process.

RESOURCE RECOVERY DISCUSSION DEFERRED

- Consultants concluded the only financially feasible option for the use of reclaimed water is within the treatment facility. This is due to a short irrigation season and the very long distances required for conveying the reclaimed water to potential customers.
- A business case for reclaimed water use is being considered through the site master planning process underway at the treatment plant.
- Further assessment and decisions will be considered by the Sewage Commission in the future.

PREFERRED CONVEYANCE OPTION

- A blended option of trenched and tunneled forcemain along Comox Road/Comox Avenue to Lazo area, was selected as the preferred option.
- Work to be undertaken as one phase, to reduce operational risk by decommissioning aging infrastructure as soon as possible.
- Conveyance upgrades identified as the biggest priority, in order to address the urgent environmental risk posed by exposed pipes at Balmoral Beach (Willemar Bluffs)







S Comox Valley

PREFERRED TREATMENT OPTION

As part of the planning process, the community provided comment on a long-list of four options for the future of wastewater treatment in the Comox Valley Sewer Service. That feedback, along with technical assessment, led to a narrowing of options until the preferred option of providing secondary treatment for all flows was selected. This option was approved by the Comox Valley Sewage Commission in December 2020.

ABOUT THE PREFERRED OPTION

The preferred option for the Liquid Waste Management Plan (LWMP) will ensure all effluent passes through secondary treatment as it does currently. However, disinfection for all flows will be added as a new component in the treatment process. The disinfection process will be designed to achieve recreational standards and the following treatment and discharge standards will apply. Upgrades and expansion to existing components will occur over time to increase capacity and comply with regulations.



SECONDARY TREATMENT FOR THE ENTIRE PLANT FLOW:

- Secondary treatment removes 90% of organic material and solids on average (note that the treatment plant currently achieves greater than 95% removal of total suspended solids (TSS) and greater than 93% removal of 5-day Biochemical Oxygen Demand (BOD5)
- Secondary treatment removes 80-95% of microplastics on average
- Meets effluent quality for provincial and federal regulations
- UV disinfection system to disinfect wastewater to not exceed 200MPN/100mL fecal coliform concentration at end of the outfall pipe. Based on dilution modelling there will be sufficient dilution to stay well below requirements for protection of shellfish.



ABOUT COMOX VALLEY SEWER CONVEYANCE PROJECT

The Comox Valley Regional District is currently planning an update to sewer conveyance infrastructure that currently services the City of Courtenay, Town of Comox and K'ómoks First Nation.



The project will replace the pipes and upgrade the pump stations that move more than 14,000 cubic metres of raw sewage each day to the sewage treatment plant on Brent Road.

This project is urgently needed to protect the beaches and waters throughout the Comox Estuary, Point Holmes, Goose Spit coastline, as well as Baynes Sound. This new system will route sewer pipes further inland where they will no longer be vulnerable to storm damage by waves, rocks and logs. The project scope was approved in Feb. 2022. Construction is expected to begin in Spring 2023 with completion in Fall 2024.






CONVEYANCE PROJECT: ROUTE ALIGNMENT

The overall project alignment includes some proposed changes from the preliminary map shared last year, including:

- Proposed rebuild and relocation of Courtenay Pump Station for seismic upgrades and climate resiliency
- 2 Moving route away from areas of archeological significance along Dyke Road and working with KFN to reduce impacts in IR#1
- 3 Use of traditional trench/ cut and cover on Comox Hill instead of drilling
- Moving portion of route from Comox Ave to Beaufort Ave to minimize traffic impacts
- 5 Further consideration of options for Lazo Marsh crossing: seeking alternative to drilling in the area.





ROUTE DETAILS: PUMP STATION + COMOX RD.

The approved project scope developed and approved by the Sewage Commission in February 2022 included key decisions about the final approach to these upgrades.

A NEW COURTENAY PUMP STATION


Replacing, rather than refurbishing, the Courtenay Pump Station was selected because:

- The cost of a new facility was the same as renovating the current one which is 40+ years old.
- It offers improved operations and maintenance access for a longer term.
- It allows the station to be relocated farther away from the estuary.

ROUTE AWAY FROM CULTURALLY SENSITIVE AREA

A section of the pipe has been rerouted from Comox Road because:

- It avoids areas already identified as having intact archeological findings – discoveries that could impact construction if found during excavation
- Our partners, KFN identified the disturbance of culturally sensitive areas as a concern
- By moving construction off Comox Road in this area, we can reduce some of the traffic impacts.



NO TUNNEL AT COMOX HILL

Using traditional cut and cover (trenching) to install the pipe at Comox Hill was selected over tunneling in this area because technical assessment and cost/benefit analysis indicated trenching is the better choice given the land elevations.



ROUTE DETAILS: TOWN OF COMOX DETAILS

The CVRD project team has been working with the Town of Comox to create a project plan that reduces the impact on the community.

MOVING CONSTRUCTION OFF COMOX AVENUE

Between Rodello and Stewart streets, the pipe will be routed off of Comox Avenue, to Beaufort Avenue.


ALIGNING WITH TOWN OF COMOX UPGRADES

Pipe construction disruption can align with road and utility upgrades planned in this area. The project team will continue working with the Town of Comox to synergize with its existing plans. Further details on these upgrades will be confirmed with the public as contracts are awarded and construction planning begins.

UPGRADE JANE PLACE PUMP STATION

In order to serve the revised pumping requirements and ensure it meets current standards, the Jane Place Pump Station will be extensively upgraded, but will remain within the same footprint.

The pipe route will follow Balmoral Avenue until it reaches the tunnel entry pit at Lazo and Torrence. The project team will work with Town staff toward a construction plan that will reduce the impact on traffic flow where possible.





ROUTE DETAILS: LAZO HILL ALIGNMENT

The forcemain will be tunneled below Lazo Hill. This confirmed alignment is the result of significant assessment, and consideration of community feedback.

Highlights

- Single shorter line from Torrence/Lazo to existing rightof-way at Morland Road
- Minimum 20-metre offset from all deep water wells in the area (as per recommendation by groundwater consultant)
- Impacts fewest properties
- Laydown on Morland/Brent Road reduces disruption
- Alignment allows for gravity flow in the pipe through Lazo Hill, reducing operational risks.





ABOUT HORIZONTAL DIRECTIONAL DRILLING


Horizontal Directional Drilling (HDD) will be used to avoid surface impacts through Lazo Hill and minimize the maximum pipe elevation to reduce lifecycle costs and risk.

HDD is typically used to install pipelines under environmental sensitive areas to avoid surface disturbance.

The contractor uses a drill rig to horizontally drill an underground pathway for the new pipe between an entry and an exit pit. This process happens in three stages.



1. Pilot Bore: A process called a pilot bore establishes the underground path for the new sewer pipe.



 Reaming Passes: The contractor will enlarge the tunnel to the final pipe size using a reamer. A bentonite-based drilling fluid keeps the borehole stabilized – the drilling mud is collected and recycled.



3. Pipe Pullback: The pipeline is assembled at surface in a long single string and is then pulled through the tunnel into its final position.




TECHNOLOGY

Engineering decisions about the method and materials for the new system provide dditional environmental protection.

GRAVITY FED LINE

- Non-pressurized flow, virtually eliminating an already very-low risk of a leak
- Allows route to remain 10m above aquifer, eliminating penetration of aquifer
- Pipe wall designed to withstand installation stress, far exceeding the zero-pressure of operational flow



MATERIAL (High Density Polyethylene)

- Shorter route allows for use of HDPE, which is far more resistant to corrosion than steel
- HDPE is more flexible and better suited to withstand seismic activity
- Continuously fused to eliminate all joints
- More resistant to abrasion and has no coating that can be damaged during installation





A lot of work has been completed to date, but there is still much to be done before this project is complete. Here's a look at upcoming key milestones to expect in the coming 18 months.



Final project scope, including routing through Lazo Hill, confirmed by the sewage commission. Tenders for construction developed, and contracts awarded.

SPRING 2022

The final project scope for the Comox Valley Conveyance Project, starting from the Courtenay Pump Station and ending at the Sewage Treatment Plant, will be shared via public events.

SPRING/SUMMER 2022

Finalize plans with Town of Comox to synergize pipe construction work with planned road and utilities upgrades in the downtown core.

FALL 2022

The CVRD will engage with residents and businesses along all points of the Comox Valley Sewer Conveyance route as part of the pre-construction planning process. This will help us to create a plan for construction that considers everyone impacted by the project.

SPRING 2023

Estimated start of construction. Communication will continue throughout the project including notice of lane closures and traffic impacts. The CVRD will work diligently with its contractor to come up with a schedule that minimizes disruption as much as possible.

FALL 2024

Following review of Stage 2 sewer plan, province formally approves the full plan.



SHARE YOUR FEEDBACK

Planning continues for the Comox Valley Sewer Conveyance Project and the CVRD is committed to engaging with the community throughout the process. Please share with us any questions, concerns or comments that you would like the project team to consider as we enter the construction planning phase.



COMMENTS, QUESTIONS, CONCERNS.









APPENDIX 2

Webinar Presentation

Comox Valley LWMP Update

April 13, 2022 Russell Dyson, CAO



About Liquid Waste Management Plans



Outline long-term plan for wastewater (sewage)



Tool for local governments, with review/approval by province



Require engineering study, environmental assessment and financial analysis




Significant public consultation required





2 of 13



























1. Pilot bore: A process called a pilot bore established the underground path for the new sewer pipe.




2. Reaming Passes: The contractor will enlarge the tunnel to the final pipe size using multiple passes of a reamer. A bentonite-based drilling fluid 'Mud' keeps the borehole stabilized – the drilling mud is collected and recycled.



3. Pipe Pullback: The pipeline is assembled at surface in a long single string and is then pulled through the tunnel into its final position.







APPENDIX 3

Print & Radio Advertisement Samples

PRINT



We've Got Big Projects Coming Down the Pipe

We are ready to share our long term plan for sewer services, including the final route for the Comox Valley Sewer Conveyance Project and future upgrades at the Sewage Treatment Plant. Join us to learn about how this plan will protect the beaches and waters throughout the Comox Estuary, Point Holmes, Goose Spit coastline and Baynes Sound.

COME LEARN MORE

Attend an Open House

Monday, April 4 4:00 pm to 6:00 pm Comox Rec Centre, 1855 Noel Ave., Comox

Join a ZOOM Webinar:

Wednesday, April 13 12:00 pm to 1:00 pm Visit link below to register

Visit www.comoxvalleyrd.ca/lwmp to learn more about the work to come, register for webinar, and sign up for updates moving forward.

Questions?

Call: **250-334-6000**

Email: engineeringservices@comoxvalleyrd.ca



Comox Valley



We've Got Big Projects Coming Down the Pipe

We are ready to share our long term plan for sewer services, including the final route for the Comox Valley Sewer Conveyance Project and future upgrades at the Sewage Treatment Plant. Join us to learn about how this plan will protect the beaches and waters throughout the Comox Estuary, Point Holmes, Goose Spit coastline and Baynes Sound.

COME LEARN MORE

Join a **ZOOM** Webinar:

Wednesday, April 13, 12:00 pm to 1:00 pm Visit link below to register

Visit www.comoxvalleyrd.ca/lwmp to learn more about the work to come, register for webinar, and sign up for updates moving forward.

Questions?

Call: 250-334-6000

Email: engineeringservices@comoxvalleyrd.ca



PRINT

We've Got Big Projects Coming Down the Pipe

We are ready to share our long term plan for sewer services, including the final route for the Comox Valley Sewer Conveyance Project and future upgrades at the Sewage Treatment Plant. Join us to learn about how this plan will protect the beaches and waters throughout the Comox Estuary, Point Holmes, Goose Spit coastline and Baynes Sound.



COME LEARN MORE

Join the **ZOOM** Webinar:

Wednesday, April 13, 12:00 pm to 1:00 pm Visit link below to register

Visit www.comoxvalleyrd.ca/lwmp to learn more about the work to come, register for webinar, and sign up for updates moving forward.

Questions?

Call: 250-334-6000

Email: engineeringservices@comoxvalleyrd.ca



SOCIAL MEDIA





RADIO

RADIO AD SCRIPT (DRAFT)

PROJECT: CV Sewer Conveyance /LWMP

MEDIA: 30 second ads

CAMPAIGN: Open House/Project Update Invitation

RUN DATES: March 28 – April 3

FREQUENCY: 6x/day



There are big things coming down the pipe for the Comox Valley Sewer Service – and the Comox Valley Regional District is ready to share the long-term plan for wastewater collection and treatment in the community.

You're invited to learn more about planning, construction and how these plans will protect beaches and waters of the area.

Join us at an in-person open house on Monday, April fourth from four p-m to six p-m, at the Comox Rec Centre. Or, register to join an online webinar April thirteenth from noon until one p-m.

For details, visit connect -C-V-R-D <dot> C-A <slash> L-W-M-P.

